

CAPISTRANO BAY DISTRICT  
AGENDA REPORT  
June 25, 2013

---

*Manager's Reports*

**ITEM J.1**

Storm Drain No. 2 – 35121 Beach Road

The high surf from earlier in the month scoured much of our beach sand and in the location of storm drain no. 2 also exposed the old existing concrete collar joint of the storm drain pipe out on the beach. While the District was aware this may eventually occur, it was not anticipated to happen this quickly.

We now have a potential human injury hazard on the beach that must be removed. The procedure is as follows:

- remove the exposed concrete collar joint (about the size of a small dumpster)
- break up and haul away
- remove all existing protruding metal pipe bracing and haul away
- install new metal pipe bracing around the remaining exposed drain pipe
- cut back the area of existing exposed old rusted corrugated metal drain pipe

This work is to be done under the existing construction permit for the storm drain project and by the same contractor who performed the drain pipe replacement last month.

Estimated cost:       \$3900  
Contractor:           Peter Drilling & Contracting Inc.

The amount exceeds the Manager's approved discretionary spending limit and must be approved by the Board of Directors.

ITEM NO. J.1



Storm Drain No. 2

ITEM NO. J.1



Storm Drain No. 2